

## SCHDULE OF WORK

**Name of Work: Proviidng Compound wall arangement for Sports Ground from Main Entrance to Volley Ball Court.**

**Ref : NITT/CoW/EMD/Civil Works/ En. No.111(120)/13-14, Dt.02.01.2014**

**Name of the Contractor/ Firm :**

**Address**

SLNo	Description	Qty	Unit	Rate (Rs)	Rate(In Words)	Amount (Rs)
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	83.00	cum			
1.1	All kinds of soil.					
2	Supplying and filling in plinth with river sand under floors, including watering, ramming, consolidating and dressing complete.	20.00	cum			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :	20.00	cum			
3.1	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)					
4	Brick work with common burnt clay modular bricks of class designation 3.5 in foundation and plinth in:					
4.1	Cement Mortar 1:6 (1 cement : 6 coarse sand).	66.00	cum			
5	12 mm cement plaster of mix :					
5.1	1:6 (1 cement: 6 fine sand)	560.00	sqm			
6	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :					
6.1	Water thinnable cement primer	560.00	sqm			

SLNo	Description	Qty	Unit	Rate (Rs)	Rate(In Words)	Amount (Rs)
7	Finishing walls with Acrylic Smooth exterior paint of required shade :					
7.1	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	560.00	sqm			
8	Brick work with common burnt clay modular bricks of class designation 3.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement Mortar 1:6	15.00	Cum			

**CONTRACTOR**

**SD  
CHIEF OF WORKS**