SCHEDULE OF WORK

Name of Work: Providing and Fixing Trilanguage Alcho pannel with Titanium sheet letter name board to T&P, Physics, Hospital, Chemistry, ICE, CA, Central Library, Mathematics, Humanities, CEESAT Departments and SS with painting box type name board to Quarters Annex.

Sl.No	Description of Work	Quantity	Unit	Rate (Rs)	Rate (In words)	Amount (Rs)
1	Providing and Fixing of trilanguage Alcho Panel name board of colour: Coffee Browm/Bergundy with Titanium sheet letter with Tamil letter height 6.25"(font type: Sentamil), Hindi letter height 6.75"(font type: Yogesh) and English letter height 6.75"(font type: swics). The leg of board consists anti corrosive oil pipe with ACP sheet folding (The number of leg is required as per site condition). The footing of pipe is 0.30m x 0.30m x 0.60m with plain cement concrete. The rate including cost of all materials and labour charges etc as per the direction of Engineer-incharge.					
1.1	(a) Training and Placement board of size : 4.50m x 0.975m		Sqm			
1.2	(b) Physics board of size: 2.40m x 0.975m	2.34	Sqm			

1.3	c) Hospital board of size: 2.40m x 0.975m	2.34	Sqm		
1.4	d) Chemistry board of size : 2.40m x 0.975m	2.34	Sqm		
1.5	(e) Instrumentation & Control Engineering board of size : 5.50m x 0.975m	5.36	Sqm		
1.6	(f) Computer Applications board of size : 3.60m x 0.975m	3.51	Sqm		
1.7	(g) Central Library board of size : 3.00m x 0.975m	2.92	Sqm		

1.8	(h) Mathematics board of size : 2.40m x 0.975m	2.34	Sqm		
1.9	(i) Humanities board of size : 2.40m x 0.975m	2.34	Sqm		
1.10	(j) CEESAT (Centre for Energy & Environmental Science & Technology) board of size: 8.40m x 0.975m	8.19	Sqm		
2.	Providing and Fixing of Alu decor company sheet name board of colour: Pearl Copper - AD82/Burgundy -AD14 with Titanium sheet letter with letter height 7.25"(font type: swics). The board consists of Acp Folding box type base of 2" thickness and steel letters box type letter white colour paint 2k company side thickness .75" etc. The leg of board consists anti corrosive oil pipe with ACP sheet folding (The number of	5.40	Sqm		

leg is required as per site condition). The footing of pipe is 0.30m x 0.30m x0.60m with plain cement concrete. The rate including cost of all			
materials and labour charges etc as per the direction of Engineer-in-charge.			

-Sd-Chief of Works Estate Maintenance Department