NATIONAL INSTITUTE OF TECHNOLOGY TIRUCHIRAPPALLI – 620 015

ESTATE MAINTENANCE DEPARTMENT

NOTICE INVITING TENDERS NO: NITT/EMD//Civi works / 2014

TENDER NOTIFICATION

Ref: NITT/EMD/ CoW/Civil works / 14-15

The **Chief of woks**, Estate Maintenance Department, NIT on behalf of The Director, NIT invites sealed item rate tenders from the approved and eligible contractors of NITT/CPWD and those in the appropriate list of Tamil Nadu state PWD, Railways, MES and BSNL for the following work. Sealed tenders will be received by the Registrar, National Institute of Technology, Tiruchirappalli-15 up to **3.00 p.m on 25.02.2015.** The tender will be **opened at 3.30. P.M** on 25.02.2015 at Registrar Office, in the presence of tenders who choose to present.

Enq No.	Est Id. No	Name of work	Estimate cost Rs.	Earnest Money Rs	Last date for Submission of the tenders	Tender cost
139	165	Civil works in Lift to Opal 'E' Amber A & B, Aquamarine A&B and Jasper Hostel.	4,08,299/-	8,000/-	25.02.2015	Rs.150/-

Tender details in this regard may also be seen in the Notice board of office of the Estate office, Estate Maintenance Dept, NIT, Trichy-15 during office hours on any working days.

The tender document can be downloaded from this institute web site

<u>www.nitt.edu/home/others/tenders/</u>. The tender cost of Rs 150/-and the Earnest money should be enclosed along with tender schedule in the form of separate demand draft from any Nationalized bank drawn in favor of "The Director, NIT, Trichy-15"

-Sd- /Chief of Works

Date.16.02.2015

SCHEDULE OF WORK

Name of Work: Civil works in lift to Opal-E, Amber A&B, Aquamarine A&B and Jasper Hostels.

Sl.No	Sub-Heads and Item of Work	Quantity	Unit	Rate (Rs)	Rate (In words)	Amount (Rs)
1.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :					
1.1	Cement mortar 1:6 (1 cement : 6 coarse sand)	3.00	Cum			
2.	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills , facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.					
2.1.	Granite of any colour and shade					
2.1.1	Area of slab upto 0.50 sqm	10.00	Sqm			

3.	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall				
	be paid for separately).				
3.1	Second class teak wood	0.50	Cum		
4	Providing and fixing plywood 4 mm thick, one				
	side decorative veneer conforming to IS: 1328 (type-1), for plain lining / cladding with necessary screws, including priming coat on unexposed surface with :				
4.1	Decorative veneer facings of approved manufacture.	65.00	Sqm		
5	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete :				
5.1	2nd class teak wood				
5.1.1	50x12 mm	160.00	Metre		

5.1.2	50 x 20 mm	120.00	Metre		
6	Steel work welded in built up sections/ framed				
	work, including cutting, hoisting, fixing in				
	position and applying a priming coat of				
	approved steel primer using structural steel etc. as required.				
6.1	In gratings, frames, guard bar, ladder, railings,	350.00	Kg		
	brackets, gates and similar works				
7	12 mm cement plaster of mix :				
7.1	1:6 (1 cement: 6 fine sand)	35.00	Sqm		
8	Painting with synthetic enamel paint of				
	approved brand and manufacture to give an				
8.1	even shade : Two or more coats on new work	15.00	Sqm		
0.1	I wo of more cours on new work	15.00	54m		

9	French spirit polishing :					
9.1	Two or more coats on new works including a coat of wood filler	65.00	Sqm			
10	Providing and fixing of 18mm thick non decorative plywood (water proof) resting on the walls etc complete.	65.00	Sqm			
	TOTAL					

-Sd-Chief of Works