

## SCHEDULE OF WORK

**Name of Work:** Providing & Fixing of Loft and cupboard arrangements to Qts.5/1,6/1 & 4/1

ITEM No	SUB-HEADS AND ITEM OF WORK	QTY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
1	CONCRETE WORK					
1.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :					
1.1.1	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	4.5	cum			
2	REINFORCED CEMENT CONCRETE					
2.1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :					
2.1.1	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	1	cum			
3	BRICK WORK					
3.1	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :					
3.1.1	cement mortar 1:4 (1 cement : 4 coarse sand)	46	sqm			
4	WOOD AND P. V. C. WORK					
4.1	Providing and fixing in wall lining flat pressed three layer (medium density) particle board or graded wood Pre-laminated one side					

	decorative lamination and other side balancing lamination Grade I, Type II, IS : 12823 marked, including priming coat on unexposed surface, with necessary fixing arrangement and screws etc. complete :					
4.1.1	18 mm thick	18	sqm			
4.1.2	25 mm thick	19	sqm			
5	STEEL WORK					
5.1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.					
5.1.1	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	120	kg			
	Sub-Total					
6	FINISHING					
6.1	12 mm cement plaster of mix :					
6.1.1	1:4 (1 cement: 4 fine sand)	90	sqm			

7	NIT MARKET RATE					
7.1	Providing and fixing of single side polished cuddapah slabs for kitchen platforms over 20mm thick base in cm 1:4 (1cement : 4sand) with joints treated walls cement mortar mixing with pigment as per the direction of Engineer-in-charge.  For 25mm to 40mm thick	12	Sq.Mtr			
						<b>TOTAL</b>

Signature of Contractor