

SCHEDULE OF WORK

Name of Work : Renovation of existing cement concrete flooring in community hall near 3rd street

ITEM NO.	SUB-HEADS AND ITEM OF WORK	QTY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
1	Providing and fixing 12 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills , facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels Granite of any colour and shade/Area of slab over 0.50 sqm	292.00	Sqm			
	TOTAL					

Sd---
Chief of woks