



TENDER NOTIFICATION

Ref No: NITT/EO/EMD/EE (E)/AE (P&D)/Enq.No:55/15-16.

Date: 19.02.2016

The Estate Officer, Estate Maintenance Department , NIT, Tiruchirappalli- 620 015 invites on behalf of The Director, NIT,Trichirappalli-620 015.Sealed item rate tenders from the approved and eligible contractors of NITT/CPWD and those in the appropriate list of Tamilnadu state PWD, Railways, MES and BSNL for the following work. Sealed tenders will be received by the **Registrar, National Institute of Technology** at his Office at National Institute of technology, Tiruchirappalli-15 up to **3.00 p.m on 04.03.2016**

Details

Enq No	Name of works & Location	Period of completion in days	Estimate cost put to tender (Rs)	Earnest Money (Rs)	Tender cost (Rs)	Last date and time of submission of Tender	Time and date of opening of Tender
55	Replacement of damaged cable fed power to Architecture dept. by new cable	120	999570	19991	525	At 3.00 PM on 04.03.2016	At 3.30 PM on 04.03.2016

The tender should accompany, Earnest Money Deposit and Tender cost as detailed above through two different Demand Drafts payable at Tiruchirappalli, Drawn in favor of **The Director, National Institute of Technology, Trichy-15**. This earnest money will be refunded to the unsuccessful tenderer or rejection of the tender or at the expiry of two months from date of tender, whichever is earlier. The earnest money will be retained in the case of the successful tenderer and will not carry any interest. Tender must be submitted in sealed covers and should be addressed to The Director, National Institute of Technology, Trichirappalli-15 and the name of the tenderer, name of the work and Ref .No. being noted on the cover. **The rates should be quoted inclusive of all taxes and duties. Submission of tender without EMD is liable to be rejected.**

**-sd-
Estate Officer**

SCHEDULE OF WORK

State Tamilnadu Enq.no.55

Branch Electrical

Name of Work : Replacement of damaged cable fed power to Architecture dept. by new cable

Division EMD

Sub Division EMC

ITEM	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
1	MV CABLE LAYING					
1.1	Supply and laying of following size Double walled Corrugated High Density Polyethylene pipe having corrugation on the outer wall and plain surface inner wall conforming to IS 14930 part- I and part -II complete with necessary HDPE fitting for protection of 1.1 KV grade under ground cable directly in ground at a depth 75cm including excavation and refilling the trench etc as required.					
1.1.1	Above 185Sq.mm upto 300Sq.mm,Size :90mm/76mm (OD/ ID)	580.00	mtrs			
	Sub-Total					
2	MV CABLE JOINTING & END TERMINATION					
2.1	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.					
2.1.1	3½ X 240 sq. mm (62mm)	2.00	Each			
	Sub-Total					
3	CIVIL ITEMS					
3.1	Providing, laying and fixing following dia RCC pipe NP2 class (light duty) in ground complete with RCC collars, jointing with cement mortar 1:2 (1 cement : 2 fine sand) including trenching (75 cm deep) and refilling etc as required.					
3.1.1	300 mm dia	18.00	metre			
	Sub-Total					
4	Supplying of Cables (MARKET ITEM)					
4.1	Supplying of following size ISI marked PVC insulated and PVC sheathed aluminium grade with armoured as required.(Make:Finolex,Gloster and Polycab)					
4.1.1	3½ X 240 Sq mm	600.00	Metre			

ITEM	SUB-HEADS AND ITEM OF WORK	QUANTITY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
	Sub-Total					
	Total					