

NATIONAL INSTITUTE OF TECHNOLOGY TIRUCHIRAPPALLI – 620 015

ESTATE MAINTENANCE DEPARTMENT

NOTICE INVITING TENDERS NO: NITT/EMD//Civi works / 2014

TENDER NOTIFICATION

Ref: NITT/EMD/ CoW/Civil works / 14-15

Date.04.03.2015

The **Chief of works**, Estate Maintenance Department, NIT on behalf of The Director, NIT invites sealed item rate tenders from the approved and eligible contractors of NITT/CPWD and those in the appropriate list of Tamil Nadu state PWD, Railways, MES and BSNL for the following work. Sealed tenders will be received by the Registrar, National Institute of Technology, Tiruchirappalli-15 up to **3.00 p.m on 17.03.2015**. The tender will be **opened at 3.30. P.M on 17.03.2015** at Registrar Office, in the presence of tenders who choose to present.

Enq No.	Est Id. No	Name of work	Estimate cost Rs.	Earnest Money Rs	Last date for Submission of the tenders	Tender cost
146	175	Providing and laying of 40mm & 32mm OD PVC pipe lines for distribution of STP water from Library corner to Sports centre & Mechanical Quadrangle	2,44,682/-	4900/-	17.03.2015	Rs.150/-

Tender details in this regard may also be seen in the Notice board of office of the Estate office, Estate Maintenance Dept, NIT, Trichy-15 during office hours on any working days.

The tender document can be downloaded from this institute web site www.nitt.edu/home/others/tenders/. The tender cost of Rs 150/-and the Earnest money should be enclosed along with tender schedule in the form of separate demand draft from any Nationalized bank drawn in favor of “The Director, NIT, Trichy-15”

-Sd- /Chief of Works

SCHEDULE OF WORK

Name of Work: Providing and laying of 40mm&32mm OD PVC pipe line s for distribution of STP water from Library corner to Sports centre & Mechanical Quadrangle

ITEM No	SUB-HEADS AND ITEM OF WORK	QTY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
1	WATER SUPPLY					
1.1	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :					
1.1.1	25 mm nominal bore	20	Each			
2	NIT MARKET RATE					
2.1	Earth work excavation & depositing on bank with initial lead of 10m and lift of 2m in all classes by soil in narrow trenches for pipe laying work including cost & conveyance of PVC rigid pipes (True Bore / Jain pipes) and specials and lowering in to trenches and laying to proper grade and alignment & jointing with PVC couplers with jointing materials and testing to the required pressure including conveyance of water for filling during testing and refilling the trenches with excavated earth on completion of work For depth up to 2m External work : 32mm OD PVC Pipes (15kg/cm ²)	150	Mtr			

2.2	<p>Earth work excavation & depositing on bank with initial lead of 10m and lift of 2m in all classes by soil in narrow trenches for pipe laying work including cost & conveyance of PVC rigid pipes (Avonplast Make) and specials and lowering in to trenches and laying to proper grade and alignment & jointing with PVC couplers with jointing materials and testing to the required pressure including conveyance of water for filling during testing and refilling the trenches with excavated earth on completion of work</p> <p>For depth up to 2m</p> <p>External work : 40mm OD PVC Pipes (15kg/cm²)</p>	900	Mtr			
2.3	<p>Supplying and fixing of PVC Saddle Piece of size 110mmx32mm including cost & conveyance of pipe to the site of work</p>	10	Each			
	TOTAL					

Signature of Contractor