

**NATIONAL INSTITUTE OF TECHNOLOGY, TIEUCHIEAPPALLI - 620015**

**ESTSTE MAINTENANCE DEPARTMENT**

Name of Work ;Providng Brick work and cut stones for OJAS Quadrangle

Name of the Agency :

Ref : NITT/CoW/EMD/Civil Works/ **Eq.No.62(68)**/14-15 ,dt.29.05.2014 Due on **10.06.2014 @ 3.00 p.m**

ITEM No	SUB-HEADS AND ITEM OF WORK	QTY	UNIT	RATE (Rs)	RATE (In Words)	AMOUNT(Rs)
1	Brick work with common burnt clay modular bricks of class designation 3.5 in foundation and plinth in:	47.00	cum			
1.1	Cement Mortar 1:6 (1 cement : 6 coarse sand).					
2	12 mm cement plaster of mix :	505.00	sqm			
2.1	1:6 (1 cement: 6 fine sand)					
3	Finishing walls with Acrylic Smooth exterior paint of required shade :					
3.1	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	505.00	sqm			
4	Supplying and laying 40 mm thick fine dressed Cut stone flooring over 20 mm (average) thick base of cement mortar 1:5 ( 1cement : 5 coarse sand) with joints finished flush. - White Cut stone	200.00	Sqm			

**Signature of Contractor**

**Sd**  
**Chief of Works**